2022R072, 2.0 MG Reservoir Level 2 Inspection Report Coconut Creek, Florida ATTACHMENT "A"

ADD ALTERNATE #1

Interior Piping

Condition Rating

Poor

Assessment

Corrosion noted on interior DIP lines.

Recommendation

Prepare surface of corroded DIP lines and coat with a polyamidoamine epoxy.

Photos



