


FIFTH THIRD BRANCH BANK



4805 Coconut Creek Parkway Coconut Creek , FL 33063







AGENDA

- Site Plan Aesthetic Design
- Sustainability Features
- Q&A / Feedback

Project Location

4805 Coconut Creek Parkway
Coconut Creek , FL 33063





Harmonious and Efficient

- Exterior Color
- Stone Masonry Base
- <10% Accent Color



New Bank Front View



New Bank SideView



Chase Bank




Bank of America




Citibank


Preservation of Natural State

- Tree & soil removal kept to a minimum
- Site complies with landscape requirements




Emergency Access











Access to Public Ways




Design of Access and Egress Drive



Stormwater Control


- Storm water will be contained on site
- Existing utilities & storm inlets are adequate for new bank building



Exterior Lighting

- Photometrics plan is complete
- No glare or direct illumination to the adjacent properties or public right of way

CALCULATION SUMMARY AT GRADE(OCCUPIED)							
LABEL	CALCTYPE	UNIT	AVG	MAX	MIN	AVG/MIN	MAX/MIN
PARKING LOTS(OCCUPIED)	ILLUMINANCE	FC	3.23	5.5	2.0	1.62	2.75
DRIVEWAY/PARKING LOTS(OCCUPIED)	ILLUMINANCE	FC	3.84	14.9	1.2	3.20	12.42
5FT TRASH ENCLOSURE(OCCUPIED)	ILLUMINANCE	FC	3.97	5.4	2.4	1.65	2.25
PROPERTY LINE	ILLUMINANCE	FC	1.18	3.7	0.0	N.A.	N.A.



EROSION CONTROL KEYED NOTES


LIMITS OF CONSTRUCTION (0.77 AC)

TRUCK WASHOUT AREA


INLET PROTECTION


CRUSHED STONE CONSTRUCTION ENTRANCE AND CONCRETE

Construction Pollution Prevention



Sd1-S SILT FENCE - TYPE SENSITIVE





Construction Site Materials Recycling

Waste Diversion Management Plan

Project Management Fifth Third Bank Acco 21-Jul-22



Waste Management Guidelines

Intent

To reduce waste disposed of in landfills by redirecting to reusing, recycling, and donating materials. This guide is intended to assist GCs with providing an accurate waste diversion tracker with supporting documentation form accredited organizations.

All projects must recycle at least 75% of all construction waste.

CBRE requires all projects to divert at least **75**% of waste from the landfill.



Managing Waste Diversion




Reporting

The following Waste Diversion documentation must be completed and returned to the CBRE PJM no later than 30 days after Turnover date.

- Completed Waste Diversion Tracker
- Supporting Documentation
- Receipts/Tickets
- o Form 187 (if furniture was donated)
- o Furniture Weight and Value Estimator (if furniture was donated)

GC (or Waste Diversion coordinator appointed by GC) is responsible in collecting all the receipts and combine the total on one final tracker.

If less than 75% or no waste was diverted- a detailed explanation is **required** in the comment section of the Waste Diversion form.



Alternative Transportation




Bike Racks




Electric Vehicle Charging Station

Minimize Heat Island Effect

- Generous Tree Canopy
- Cool Roof White TPO





Innovative Water Technologies


- Battery-Powered Faucets
- Efficient Toilets
- Water Fountain with Touchless Bottle Filler.






Energy Efficiencies

- Solar Power Panels
- Efficient HVAC System





New Branch Bank September 25, 2025 City Commission Meeting

Conspicuous Display of Green Technology

• Rain Garden

